SRI SRINIVASA GROUP OF INDUSTRIES · ISO 9001:2015

RCC spun pipes, NP2 and NP3.

Sri Srinivasa Spun Pipe Industries: RCC spun pipes, precast and cement products from six manufacturing units in Telangana.

40+	6	4,000–6,000	500+
Years of industrial experience	Manufacturing units in Telangana	Pipes a month, capacity	Truck dispatches a month

Pipe sizes

	DIAMETER	CLASS	LENGTH	JOINT	LISTED AS
○	6 in	–	2 m	Socket	Socket
○	8 in	–	2 m	Socket	Socket
○	9 in	–	2 m	Socket	Socket
○	10 in	–	–*	Socket	Socket
○	12 in	–	2 m	Socket	Socket
○	300 mm	NP2 · NP3	2.5 m	Socket · Groove	NP2 socket · NP3 socket · NP3 groove
○	450 mm	NP2 · NP3	2.5 m	Socket · Groove · Plain	NP2 plain · NP2 socket · NP3 socket · NP3 groove
○	600 mm	NP2 · NP3	2.5 m	Socket · Groove · Plain	NP2 plain · NP2 socket · NP3 socket · NP3 groove
○	750 mm	NP2/NP3	2.5 m	–	NP2/NP3, confirm on enquiry
○	800 mm	NP3	2.5 m	Groove	NP3 groove
○	900 mm	NP2 · NP3	2.5 m	Socket · Groove · Plain	NP2 plain · NP3 socket · NP3 groove
○	1000 mm	NP3	2.5 m	Groove	NP3 groove
○	1200 mm	NP2 · NP3	2.5 m	Socket · Groove	NP2 socket · NP3 socket · NP3 groove
○	1400 mm	NP3	2.5 m	Groove	NP3 groove
○	1600 mm	NP3	2.5 m	Groove	NP3 groove

As listed in our company profiles. “Groove” is listed as “GRUE”. 750 mm class to confirm on enquiry. * The 10 in socket pipe’s length is not listed; we confirm it when you enquire. Rings are drawn to relative diameter. Diameters are given as the documents list them (inch sizes are not converted).

APPLICATIONS

National highway drainage · Municipal sewage · Stormwater networks · Irrigation systems

QUALITY

Compression testing · Dimensional inspection · Load testing · Batch certification · IS standard compliance · ISO standards

SRI SRINIVASA SPUN PIPE INDUSTRIES · SRI SRINIVASA GROUP OF INDUSTRIES
+91 98496 88266 · +91 87128 88529 · RAKESH.CPM.MATERIALS@GMAIL.COM

Plant

- Automated spinning machines
- Concrete batching plants
- Steel reinforcement fabrication
- Curing yards
- Testing laboratory
- Storage yards
- Transport logistics

Six units

01 **Sri Srinivasa Spun Pipe Industries**
Sy. No. 238, Kothlapur Road, Pothireddipally, Sangareddy, Telangana 502295

02 **Sri Venkateshwara Cement Works**
1-68/5, Anantharedy Colony, Pothireddypally, Kothlapur Road, Sangareddy, Telangana 502295

03 **Sri Srinivasa Spun Pipe Industries**
Kothlapur Road, Sangareddy, Telangana 502295

04 **Sri Srinivasa Spun Pipe Industries**
Sy. No. 47/AA/2, Ramanthapur, Shankarpally, Ranga Reddy, Telangana 501203

05 **SS Balaji Spun Pipe Industries**
Sy. No. 99/D, Nidigonda, Raghunathpalle, Jangaon Dist., Telangana 506244

06 **SVR Spun Pipe Industries**
Sy. No. 145/AA1/1, Aloor Village, Chevella Mandal, Ranga Reddy Dist., Telangana

Also cast

SFRC manholes & covers	10 ton · 20 ton
RCC rings	1.5 ft to 4 ft · 4×4 · for sumps and tanks
Dividers & kerb stones	14×4×24 in · 16×4×24 in · curve stone 14 & 16 in
Solid concrete blocks	4×8×16 in · 8×6×12 in · 8×4×16 in
Fencing poles	6–10 ft · 3½ to 6 in square · bend, kadi, Y poles · 5–12 ft custom
Dragon fruit poles	8 ft 4×5 in · trellis systems
Precast compound walls	Posts with brick- or biscuit-type plates
Bench sets	5 ft · 6 ft · parks, apartments, grounds
Arrow marks	Highway direction & kilometre markers

REQUEST A QUOTE

Call, or email your requirement.

Tell us the diameter, class, quantity and site location.

+91 98496 88266
+91 87128 88529
rakesh.cpm.materials@gmail.com
RAKESH GUMMADIDALA · MANAGING DIRECTOR

All sizes, classes and lengths as listed in our company profiles; confirm on enquiry. Catalogue generated October 2026 from the website's spec table.